SCHEDULE-B

***Name of the Work*: Tender for the work of replacing of 200 /230 mm dia SW pipeline by 300 mm dia RCC NP3 pipeline at 9th Cross, Hilal Nagar, 6th main,3rd block, HBR layout under HBR S/stn, of AEEE-2-1 sub division. Action Plan ID NO-(E-2-2023-SWPL-005).**

Sl. No	Particulars	Unit	Total quantity	Rate
1	Dismantling of Flexible pavements and disposal of dismantled materials and stacking serviceable and unserviceable materials separately, By Mechanical Means Bituminous course (BWSSB SR 2023-24 Vol-3, P. No.-11, I.No.2.18)	m^3	43.27	322.00
2	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. (CSR 23-24 Vol - I, Sl.No: 1.17, Pg.No.10)All kinds of soil depth upto 1.5m ,300mm dia RCC Np3.	m^3	266.22	262
2a.	Depth exceeding 1.5 m, but not exceeding 3 m ,300mm dia RCC Np3.	m^3	95.95	331
3	Supplying S&S RCC SPUN / VIBRATED CAST PIPES (REINFORCED) pipes NP-3 Class conforming to IS:458-1988 with latest amendments using ordinary portland cement, for sanitary works and conveying to work site, rolling and lowering into trenches, laying true to line and level including loading and unloading at both destinations and jointing of pipes and specials, perfect linking of joints with jack to correct position including cost of jointing materials, i.e, rubber rings conforming to IS: 5382 for S&S RCC pipes, with all leads and lifts as directed and giving necessary hydraulic test as per ISS to the required pressure and commissioning etc. complete. (Contractor will make his own arrangements for procuring water for testing). Before the execution of the work, the contractor shall carry out the survey. (CSR 23-24 Vol - V, Sl.No: 16.3, Pg. No. 188) 300mm dia RCC Np3.	m	249.2	1332.00
4	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m, and lift upto 1.5 m. Including cost of all labour complete as per specifications (BWSSB SR 2023-24 VOL-I P.No.7, I.No. 1.1)	m^3	377.01	160.00
5	Providing and constructing “WIRE CUT BRICK MACHINEHOLE CHAMBERS” using Portland/Pozzolana cement, conical in shape at top, with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15M alround the chamber. Construct Brick masonry in CM 1:4, 340 mm thick, with wirecut bricks of approved quality, plaster inside and out side with CM 1:3, 12mm thick, except for the conical surface outside where the plaster thickness shall be 20mm. Slope inside to be 1:6 in the concrete towards central drain and finished smooth. Fixing of pipes in CC 1:2:4 with graded metal of 20mm and down size. Supplying and fixing SFRC Machinehole frame and cover (Heavy Duty) conforming to IS:12592 with latest amendment, in CC 1:2:4. Supplying and fixing footsteps made of 12mm dia. steel bars (Fe-500) with 3mm thick plastic encapsulation (IS-10910). The footsteps shall be fixed 30cms apart and on CC block embeded to masonry wall. The whole works include watering, curing, barricading, danger lighting, pouring tar over MH frame and cover, cost of tar, shoring, strutting, de watering, engraving Machinehole number with flow direction on the inner conical surface etc. as per the			

	drawing etc. as per technical specifications and for the following diameters and depth etc. for 1.2mm diaCirc. B M.H: 1.2m dia BWSSB SR 2023-24 Vol-5 Page no 192 Item No16.15			
5a	1.0 m depth manhole NMH 1	No	1	29047.00
5b	1.20 m depth manhole NMH 2	No	1	31370.00
5c	1.40 m depth manhole NMH 3	No	1	36535.00
5d	1.60 m depth manhole NMH 4	No	1	41568.00
5e	1.80 m depth manhole NMH 5	No	1	44888.00
5f	2.00 m depth manhole NMH 6	No	1	60784.00
5g	2.10 m depth manhole NMH 7	No	1	63638.00
5h	2.30 m depth manhole NMH 8	No	1	69344.00
5i	2.50 m depth manhole NMH 9	No	1	75050.00
6	Dismantling the damaged or collapsed Machine hole, conical in shape, and reconstructing the same for the same dimensions, with machine made wire cut brick in CM 1:4 with ordinary Portland cement etc. as per design and specifications. The existing ring, cover and CC beeding to be used. For 1.2M dia:16.25.1,vol-5 p.no.197			
	1.5 m depth manhole NMH 10	No	1	23935.00
7	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. (BWSSB SR 2023-24 Page no-26, Vol-3, Item no-4.17)	m^3	32.45	2559
8	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 kg/m2 using mechanical means BWSSB SR 2023-24 Page no-31 Vol-3, Item no-5.1	m^2	216.34	41
9	Providing and laying Bituminous Macadam with 120 tph capacity hot mix plant batch type using crushed aggregates of specified grading premixed with bituminous binder VG-30 @ 3.3% by weight of mix, transported to site, laid over a previously prepared surface with mechanical paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction (BWSSB 2023-24 Page no-31, Item no-5.6, Vol-3	m^3	21.63	7536
9	Removal of Unserviceable Soil with Disposal upto a suitable distance as directed by the Engineer in charge of work (PWD SR 2023-24, Vol-3, Page no-17, item no-3.10)	m^3	28.43	85
10	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete (BWSSB SR 2023-24, Vol-5, Page no-120, 10.14			
	110mm(weight of pipe -1.315 kg)	m	25	282
11	Supply and delivery at site special moulded variety PVC bend as per IS 7834/ 1987 and fabricated as per IG124/ 1984 with ISI mark with its latest amendments 110 mm dia PVC BEND (Page no118	Each	25	492

	Vol-5)			
12	Supply and delivery at site special moulded variety PVC reducer as per IS 7834/ 1987 and fabricated as per IG124/ 1984 with ISI mark with its latest amendments 110 mm dia PVC REDUCER (Page no119 Vol-5)	Each	25	261
11	Dewatering the sewage / storm water by using reqired HP submersible pump for the diversion of storm / sewage during the execution of work. Considering for one Pump (BWSSB SR 2023-24, Page No-206, Item no-16.55			
	10 Hp	Hr	15	426

Executive Engineer

Water Supply & Sanitary division (East)-2,
BWSSB,HRBR 1st Block Kalyan nagar,
Bangalore-560043